Items.	*Per.*	*Quantity.*	*Rate.* Rs. a. p.
WEIR CHANNEL.			
Earthwork excavation in soft rock	C. yd.	3,200	0 5 0
Blasting rock	„	424	1 8 0
Excavation, ordinary soil	„	3,156	0 2 0
Revetting with blasted stones		Lump sum	100 0 0
WIDENING THE ROAD TUNNEL.			
Earthwork	C. yd	209	0 2 0
Burnt stone in chunam	C. ft.	747	0 3 0
Burnt stone slabs, dressed	S. ft.	88	0 5 0
Pointing with chunam	Sq.	2·80	2 0 0
Dressing over parapet walls	S. ft.	115	0 2 0
Dismantling abutment and wings		Lump sum	5 0 0
Metalling over road wing	S. yd.	80	0 2 0
Earthwork filling road	C. yd.	27	0 1 6
Rough stone work, new	„	34	1 0 0
SLUICE CHANNEL.			
Earthwork excavation channel	C. yd.	2,481	0 2 0
Do foundation	„	25	0 2 0
Concrete in surki	C. ft.	435	0 3 0
Do in cement	„	25	0 12 0
Burnt stone in chunam	C. ft.	1,367	0 3 0
Pointing with chunam	Sq.	7·63	2 0 0
Burnt stone slabs, dressed	S. ft.	430	0 5 0
Rough stone work, new	C. yd.	40	1 0 0
Dismantling sluice ... ... / Relieving weirs		Lump sum	380 0 0

J. E. A. D'CRUZ,
Executive Engineer.

TUMKUR DIVISION.

FORM OF ADVERTISEMENT.

Dated 20th February 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 15th March 1913, for restoring Puravara Suppadevarakere, Registered No. 229, Maddagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Puravara Suppadevarakere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity
	Bund R. L. 55·00 and 6 feet top width		
1	Earthwork to bund	C. yd.	5,049
2	Earthwork breach filling	„	7,623
3	Removing sand silt from breach	„	1,870
4	New stone work	„	1,333
5	Old stone work	„	258
6	Grade stones	No.	28
7	Index stones	„	28
8	Gauge stone (14 feet high)	„	1
9	B. M. stones	„	2
10	Gravel backing behind revetment...	C. yd.	731
11	Turfing	S. yd.	6,205
12	Under pining the old stone revetment	L. S.	Rs.
	Sluice.		
13	Repairing the existing sluice	L. S.	Rs.
	Waste weir 148 feet long at R. L. 55·00.		
14	Earthwork clearing draft and approaches and excavating foundation and the earth used for wing bund and main bund.	L. S.	Rs.
15	Burnt brick in surki mortar	C. ft.	1,448
16	Plastering with surki mortar	Sq. ft.	4·51
17	Burnt stone slabs	„	444
18	Rough stone work apron	C. yd.	219
19	Old stone work	„	73

K. PONNAPPA,
Executive Engineer.

MYSORE DIVISION.

Dated 12th February 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive ...neer, Mysore Division, up to 15th March 1913, for improving the roof of Sandalkoti ...nsur. An approximate estimate of quantities is given below. These quantities are ...aranteed. The work should be completed by the end of May 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engi... Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the ...ive Engineer. The tenders should be accompanied by a statement in the form given ...showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred ... cash or Government Promissory Notes, as earnest money, and be superscribed ... for improving the roof of Sandalkoti at Hunsur," in default of which, tenders will ...ed.

5. The final acceptance of any tender will rest with Chief Engineer, who does not ...self to accept the lowest or any tender or to assign any reason whatever for the ... of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be ... to execute the usual contract bond; in default of which, his tender will be consider... and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be ...he notice board in the Executive Engineer's Office in due course. No enquiries ...the acceptance or rejection of a tender will receive any reply.